

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-00431-00-00
Spot: NENESW Sec/Twnshp/Rge: 28-29S-33W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ELLIOTT Well #: 3
County: HASKELL Total Vertical Depth: 2820 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 W OKLAHOMA AVE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	680		WITH 600 SX CMT
PROD	5.5	2812	0	WITH 750 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/05/2011 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: KEVIN STRUBE Company: BP AMERICA Phone: (620) 356-1237

Proposed Plugging Method: RIH W/TBG TO 1300' & PUMP 25 SX CMT WITH 200# HULLS. SHUT IN FOR 3 HOURS. TAG TOC & IF HOLDING FILL 5 1/2" CASING TO SURFACE WITH CMT & CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/05/2011 2:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

WELL HAS TBG FISH @ 1314' & ROD FISH @ 600'. TAGGED TOP OF TBG FISH @ 1348'. PUMPED 25 SX CMT WITH CCL & 200# HULLS @ 1323'. POOH WITH TBG & LET SET FOR 2 HOURS. RIH WITH TBG & TAGGED TOC @ 1230'. PUMPED 125 SX CMT FILLING 5 1/2" CASING TO SURFACE. TIE ONTO 5 1/2" X 10 3/4" ANNULUS & PUMPED 2 SX CMT. PRESSURED TO 350 PSI.

Perfs:

Top	Bot	Thru	Comments
2714	2738		
2680	2691		
2636	2678		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

RECEIVED
APR 11 2011

KCC WICHITA

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED

APR - 7 2011

KCC DODGE CITY

Form 2/23