

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20803-00-00
Spot: SWNENENE Sec/Twnshp/Rge: 10-29S-13W
440 feet from N Section Line, 400 feet from E Section Line
Lease Name: SWISHER UNIT-BREHM Well #: 1
County: PRATT Total Vertical Depth: 4770 feet

Operator License No.: 8045
Op Name: C & B OPERATING INC.
Address: PO BOX 65
ST JOHN, KS 67576

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4250		WITH 2 SX CMT
CIBP		4350		
SURF	8.625	485		WITH 350 SX CMT
PROD	5.5	4769	1540	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/30/2011 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: JEFFREY A. BURK Company: C & B OPERATING Phone: (316) 269-2015

Proposed Plugging Method: Set a CIBP @ 4250', then; 1st plug @ 860' w/ 12 sxs of gel & 50 sxs of cement, 2nd plug @ 510' w/ 50 sxs if cement, then the 3rd plug @ 40' w/ cement to surface. NOTE: Cement is 60/40 poz (4% gel).

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2011 10:10 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4250' WITH 2 SX CMT ON TOP WITH DUMP BAILER. 1ST PLUG AT 855' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 537' WITH 50 SX CMT. 3RD PLUG AT 45' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4726	4736		ARBUCKLE
4616	4619		SIMPSON

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC SERVICE.

Plugged through: CSG

District: 01

RECEIVED
APR - 5 2011

KCC DODGE CITY

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED
APR 12 2011

KCC WICHITA