

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20568-00-00
Spot: SWSW Sec/Twnshp/Rge: 14-27S-34W
644 feet from S Section Line, 4554 feet from E Section Line
Lease Name: OLIVER Well #: 2-14
County: HASKELL Total Vertical Depth: 5276 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1936		WITH 710 SX CMT
DVT		3164		WITH 315 SX CMT
PROD	5.5	5276	1678	WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2011 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: RIH WITH TBG TO 5100' & SPOT 40 SX CMT WITH 250# HULLS. SHOOT 5 1/2" CASING & POOH WITH CASING. RIH WITH TBG & PUMP 50 SX CMT AT CASING STUB, 50 SX CMT AT 900'. 10 SX CMT AT 40'.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/04/2011 2:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

RIH WITH TBG TO 5100' & SPOT 40 SX CMT WITH 250# HULLS. SHOOT 5 1/2" CASING AT 1658'. POOH WITH CASING. 1ST PLUG RIH WITH TBG & PUMP 50 SX CMT AT 1650'. 2ND PLUG AT 900' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5134	5138		ST LOUIS
5100	5104		ST GENEVIEVE

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED

APR 11 2011

KCC WICHITA

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED

APR -7 2011

KCC DODGE CITY

Form CP-2/3