

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-20381#00-01  
Spot: W2NENW Sec/Twnshp/Rge: 8-33S-4W  
660 feet from N Section Line, 1650 feet from W Section Line  
Lease Name: WUNSCH Well #: 1  
County: SUMNER Total Vertical Depth: 4700 feet

Operator License No.: 5039  
Op Name: AGV CORP.  
Address: PO BOX 377  
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	3200		
CIBP	4.5	3595		
SURF	8.625	272		225 sx cmt
PROD	4.5	3850	2680	150 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/06/2010 8:00 AM  
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC  
Proposal Rcvd. from: DAVE MILLER Company: AGV Phone: (316) 215-1683

Proposed Plugging Method: CIBP 3200' AND 2 SKS CMT. REC. CASING, 35 SKS 850, 35 SKS 500, CIRC CMT 330-0

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/06/2010 3:10 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:  
THE PERFS WERE COVERED WITH A CIBP AT 3200', AND CAPPED WITH 2 SKS OF CMT. THE CASING WAS RECOVERED FROM 2680' AND PULLED TO 850', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED T 500', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 330', WHERE CMT WAS CIRC'D TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3660	3664	CSG	
3262	3265	CSG	

RECEIVED  
APR 11 2011  
KCC WICHITA

Remarks: BASIC WELL CEMENTING 60/40 4% GEL  
Plugged through: CSG

District: 02 Signed  (TECHNICIAN)