

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-20830-00-00  
Spot: NWNWSE Sec/Twnshp/Rge: 14-20S-3W  
2267 feet from S Section Line, 2253 feet from E Section Line  
Lease Name: JUHNKE Well #: A-2  
County: MCPHERSON Total Vertical Depth: 3300 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	258		200 SX
PROD	4.5	3299	1012	250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/05/2011 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/05/2011 10:00 AM KCC Agent: SHANE JONES

Actual Plugging Report:

4/4/11 KELSO'S DROPPED SAND. KELSO'S TAGGED SAND @ 2885' AND CAPPED W/4SX. THEY RIPPED CASING @ 1012'. THEY PULLED CASING UP TO 512' AND SHUT DOWN FOR THE DAY. 4/5/11 COPELAND TIED ON TO CASING AND BROKE CIRCULATION WITH WATER. THEY SWITCHED TO CEMENT AND CIRCULATED CEMENT FROM 512' TO SURFACE. KELSO'S PULLED THE REST OF THE CASING. HOLE STANDING FULL. FINISHED @ 10:00 AM COPELAND USED 325 SX 60/40 POS W 4% GEL TK #37646. 4/6/11 I CHECKED TOP PLUG HOLE STILL STANDING FULL.


Perfs:

Top	Bot	Thru	Comments
3038	3049	CSG	

RECEIVED  
APR 13 2011  
KCC WICHITA

Remarks:  
Plugged through: TBG

District: 02

Signed  (TECHNICIAN)