

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-00405-00-00  
Spot: NWNESW Sec/Twnshp/Rge: 2-20S-4W  
2271 feet from S Section Line, 3541 feet from E Section Line  
Lease Name: SOUTHWEST COLLEGE Well #: 1  
County: MCPHERSON Total Vertical Depth: 3792 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	575		
PROD	5.5	3792		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/31/2011 10:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS.

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/01/2011 11:15 AM KCC Agent: SHANE JONES

Actual Plugging Report:

3/30/11 KELSO'S DROPPED SAND. 3/31/11 KELSO'S TAGGED SAND @ 3460' AND CAPPED W/5 SX. THEY PERFED @ 625'. THEY RAN TUBING TO 625'. COPELAND TIED ON AND COULD NOT GET CIRCULATION. THEY CAN NOT FIT 1" DOWN BETWEEN THE 5 1/2" & THE 8 5/8". IT WAS DECIDED TO HAVE PERFORATORS CAME BACK AND SHOOT OFF CASING @ 625' AND PULL PIPE. PERFORATORS OUT AND SHOOT OFF PIPE @ 586' PIPE NOT FREE. COPELAND HOOKED BACK UP AND TRIED TO CIRCULATE. THEY PUMPED INTO IT @ 5.7 BBL/MIN AT 50 PSI, BUT DID NOT CIRCULATE. THEY THEN CAME UP INSIDE THE SURFACE PIPE AND SHOOT OFF CASING @ 546'. PIPE STILL NOT FREE. IT WAS DISCUSSED WITH J KLOCK AND OPERATOR GIVEN PERMISSION TO PERFORATE @ 250' TO TRY AND CIRCULATE UP BACK SIDE. STILL CAN NOT GET CIRCULATION. OPERATOR DECIDED TO MIX UP 100SX PLUG WITH HULLS AND PUMP IT DOWN THE CASING. THEN MIX UP 50 SX WITH 3 SX HULLS AND PUMP DOWN BACKSIDE. THEN LET SET OVER NIGHT AND COME OUT AND TAG IN THE MORNING. 4/1/11 KELSO'S RAN TUBING IN AND TAGGED @ 552'. COPELAND HOOKED ON AND WAS ABLE TO BREAK CIRCULATION. COPELAND SWITCHED TO CEMENT AND CIRCULATED TO TOP OF 5 1/2". THEY SHUT IN THE 5 1/2" AND GOT CEMENT TO CIRCULATE UP THE BACK SIDE W/220 SX. KELSO'S PULLED PIPE AND WE TOPPED OFF THE HOLE WITH ANOTHER 25 SX. FINISHING @ 11:15 AM. COPELAND USED 395 SX 60/40 POS W 4% GEL TK #37641. 4/4/11 VC CHECHED TOP PLUG AND FOUND IT 1' DOWN.

Perfs:

Top	Bot	Thru	Comments
3515	3520	CSG	MISSISSIPPIAN

RECEIVED  
APR 13 2011  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)