

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22763-00-01
Spot: SWSENWSW Sec/Twnshp/Rge: 26-33S-38W
1590 feet from S Section Line, 740 feet from W Section Line
Lease Name: DEMUTH Well #: 1-26X
County: STEVENS Total Vertical Depth: 1775 feet

Operator License No.: 9262
Op Name: LOWRY EXPLORATION, INC.
Address: SUITE 306 427 S BOSTON AVE
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	13.38	610		

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 04/01/2011 1:00 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: R.G. LOWRY Company: LOWRY EXPLORATION Phone: (918) 587-5094

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 04/04/2011 1:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

Perfs:

270' DRILL COLLARS LEFT IN HOLE. TOP OF FISH @ 1200'. 4/1/11: 1ST PLUG MIRU WITH POWER SWIVEL. TIH W/ 12 1/4 BIT & 4 X 4" D.C. TAG SOFT CMT @ 610'. ATTEMPTED TO LOAD HOLE. BROKE DOWN AT 200#. 4/2/11 TIH WITH 2 7/8" TO 608'. PUMPED 50 SX CMT. WAIT ON CMT 2 1/2 HOURS. TAG TOP OF CMT AT 625'. 2ND PLUG PUMPED 75 SX CMT AT 622'. TOOH. SDON. 4/4/11: 3RD PLUG TAG TOC @ 581'. PULL TO 285' & PUMP 50 SX CMT. 4TH PLUG PULL TO 60' & PUMP 30 SX CMT.

RECEIVED
APR 12 2011
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL 4% CC BY ALLIED & HOWCO.

Plugged through: DP

District: 01

Signed

Steve Durrant

(TECHNICIAN)

RECEIVED

APR - 8 2011

KCC DODGE CITY