

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21199-00-01
Spot: SWNESE Sec/Twnshp/Rge: 19-33S-25W
2020 feet from S Section Line, 500 feet from E Section Line
Lease Name: THEIS Well #: 1-19
County: CLARK Total Vertical Depth: 7385 feet

Operator License No.: 5254
Op Name: MIDCO EXPLORATION, INC.
Address: 414 PLAZA DR STE 204
WESTMONT, IL 60559

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6948		WITH 2 SX CMT
SURF	8.625	792		WITH 400 SX CMT
PROD	5.5	7367	2510	WITH 325 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/30/2011 9:00 AM
Plug Co. License No.: 32297 Plug Co. Name: SUPERIOR SERVICING, INC.
Proposal Rcvd. from: DAVID MAYFIELD Company: MIDCO EXPLORATION Phone: (620) 786-9166

Proposed Plugging Method: SET CIBP @ 6948' WITH 2 SX CMT. PLUG AT 810' WITH 15 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2011 11:00 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 6948' WITH 2 SX CMT. 1ST PLUG RUN TBG TO 828'. LOAD HOLE WITH GEL WATER & PUMP 75 SX CMT. 2ND PLUG PULL TO 333' & PUMP 50 SX CMT. 3RD PLUG PULL TO 60' & PUMP 20 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
7049	7053		
7036	7041		
6998	7002		
6993	6996		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED
APR 07 2011
KCC WICHITA

District: 01

Signed Jerry W. Stapleton
JERRY W. STAPLETON (TECHNICIAN)

RECEIVED
APR - 5 2011
KCC DODGE CITY