

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20742-00-02
Spot: NWNWNW Sec/Twnshp/Rge: 25-28S-16W
4952 feet from S Section Line, 4954 feet from E Section Line
Lease Name: PEOPLES BANK Well #: 1-25
County: KIOWA Total Vertical Depth: 4765 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	440		
PROD	5.5	4666	2230	WITH 125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/12/2010 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: KEVIN FISCHER Company: APOLLO ENERGIES Phone: (620) 672-9001

Proposed Plugging Method: SAND TO 4490' WITH 5 SX CMT. PLUG AT 1070' WITH 15 SX GEL & 50 SX CMT. PLUG AT 470' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/12/2010 4:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 4490' WITH 5 SX CMT. 1ST PLUG AT 1050' WITH 15 SX GEL, 100# HULLS, & 50 SX CMT. 2ND PLUG AT 470' WITH 100# HULLS & 50 SX CMT. 3RD PLUG AT 60' WITH 25 SX CMT. CMT CIRCULATED BUT FELL BACK. TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4642	4660		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

RECEIVED
OCT 22 2010
KCC WICHITA

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
OCT 19 2010
KCC DODGE CITY

Form CP-2/3