

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-02681-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 25-20S-9W  
981 feet from S Section Line, 3663 feet from E Section Line  
Lease Name: TOBIAS Well #: 15  
County: RICE Total Vertical Depth: 3360 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3283		
CIBP	5.5	3336		
SURF	8.625	203		
PROD	5.5	3353		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/03/2010 1:00 PM  
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC  
Proposal Rcvd. from: BOB GRANT Company: BEREXCO LLC Phone: (316) 772-8160

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/04/2010 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, ATTEMPT TO TAG BOTTOM--ENCOUNTERED OBSTRUCTION AT 1043' WITH TUBING. RUN IN A MILL AND TURNED DOWN TO 1045'. TRIED SECOND TIME AND GOT TO 1054'. TRIED THIRD TIME AND GOT TO 1064'. BELIEVED TO BE OUT OF CASING AT 1064'. PERFORATE AT 700' AND 253'. RUN TUBING TO 1064' AND PUMP 50 SX'S COMMON CEMENT WITH 150#'S COTTON HULLS TRAILING IN WITH. PULL TUBING TO 700' AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING TO 253' AND ATTEMPT TO CIRCULATE CEMENT TO SURFACE. DID NTO GET FULL CIRCULATION. SHUT DOWN FOR DAY. CAME BACK ON 11-4-2010 TAGGED CEMENT AT 812'. PUMPED 50 MORE SX'S COMMON CEMENT WITH 200#'S COTTON HULLS AND GOOD CIRCULATION. PULL TUBING TO 255' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3353	3360	OH	
3298	3303	CSG	
3270	3274	CSG	
3262	3265	CSG	
3224	3244	CSG	

Remarks: ALLIED CEMENT TICKET #036867. PERF TECH TICKET #7694.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

RECEIVED

DEC 02 2010

Form CP-2/3

KCC WICHITA