

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-10113-00-00
Spot: SWSESW Sec/Twnshp/Rge: 33-31S-1W
330 feet from S Section Line, 3630 feet from E Section Line
Lease Name: WELLINGTON UNIT Well #: 85
County: SUMNER Total Vertical Depth: 3699 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	7	450		
CIBP		3600		
SURF	10	329		137 SX
PROD	7	3645		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/09/2009 8:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: JASON BRUNS Company: BEREXCO LLC Phone: (620) 886-2080

Proposed Plugging Method: SET CIBP AT 3600' AND CAP WITH 2 SKS OF CMT. PERF 4 HOLES AT 400' AND CIRC CMT TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/06/2009 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 3600' AND CAPPED WITH 2 SKS OF CMT. A SECOND CIBP WAS SET AT 450' AND CAPPED WITH 2 SKS OF CMT. THE CASING WAS PERFED AT 400' AND CMT WAS CIRCULATED TO SURFACE.

Perfs:			
Top	Bot	Thru	Comments
3645	3699	OH	

Remarks: ALLIED CEMENTING 60/40 4% GEL 300 SKS
Plugged through: CSG

RECEIVED
DEC 03 2010
KCC WICHITA

District: 02

Signed [Signature]
(TECHNICIAN)

SK