

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22041-00-00
Spot: NENESE Sec/Twnshp/Rge: 31-10S-16W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: GEORGE Well #: 3
County: ROOKS Total Vertical Depth: 3565 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	250	0	175 sx
PROD	4.5	3560	0	250 sxs

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/05/2010 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KENNETH VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 200# hulls.
Holes in the casing.
Seven joints of tubing on a keylo-socket.
Rods stuck in the hole. Tubing to 3100'-1500' out of hole.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/05/2010 2:20 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Gasclar Well Service RIH with tubing to 1500'.
Allied rigged to tubing and pumped 100 sxs neat cement - followed with 100 sxs cement and 200# hulls mixed in to circulate cement to surface.
Pulled tubing - rigged to 8 5/8" casing with a swedge - pumped 30 sxs cement.
Max. P.S.I. 150#. Blew small hole on head - no shut in pressure.
Topped off 4 1/2" casing with 40 sxs cement.

Top	Bot	Thru	Comments
3450	3472		
3388	3394		
3366	3370		
3340	3344		
3318	3324		

Remarks: ALLIED CEMENTING COMPANY-TICKET #33978.

Plugged through: TBG

District: 04

Signed  (TECHNICIAN) . CM

RECEIVED
NOV 17 2010 Form CP-2/3
KCC WICHITA

NOV 12 2010