

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-091-22166-00-00
Spot: NWSESENE Sec/Twnshp/Rge: 31-14S-22E
3029 feet from S Section Line, 379 feet from E Section Line
Lease Name: KNABE Well #: 1A
County: JOHNSON Total Vertical Depth: 940 feet

Operator License No.: 34348
Op Name: BLUE DIAMOND HOLDINGS, LLC
Address: 4595 K-33 HWY PO BOX 128
WELLSVILLE, KS 66092

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 6.25 | 20 | | 5 SX |
| PROD | 2.875 | 929 | | 125 SX |

Well Type: EOR UIC Docket No: E25925.1 Date/Time to Plug: 10/13/2010 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JIM HOEHN Company: BLUE DIAMOND HOLDINGS, LLC Phone: (785) 883-4057

Proposed Plugging Method: 10SX CEMENT AT CASING TD, 10SX CEMENT AT ~600FT, CEMENT FROM 250FT TO SURFACE. CUT OFF CASING AT DEPTH REQUIRED BY STATE, BACKFILL.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 10/13/2010 12:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

RAN 1" PIPE DOWN TO 940' INSIDE THE 2 7/8" CASING AND PUMPED 35 SACKS OF CEMENT TO THE SURFACE. HOOKED ON TO 2 7/8" CASING AND SQUEEZED 10 SACKS OF CEMENT.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|--------------|
| 882 | 890 | | BARTLESVILLE |

RECEIVED
NOV 19 2010
KCC WICHITA

RECEIVED
NOV 17 2010 TCH
KCC Chanute Dist. #3

Remarks:
Plugged through: TBG

District: 03

Signed Taylor C. Herman
(TECHNICIAN)