

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23902-00-00  
Spot: NWNESENE Sec/Twnshp/Rge: 30-8S-19W  
1370 feet from N Section Line, 590 feet from E Section Line  
Lease Name: PAUL LOWRY Well #: 1  
County: ROOKS Total Vertical Depth: 3500 feet

Operator License No.: 31569  
Op Name: BACH, JASON DBA BACH OIL PRODUC  
Address: PO BOX 723  
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	210		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/14/2010 3:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: ANDY DINKEL Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN WitnessType: NONE  
Date/Time Plugging Completed: 11/14/2010 4:30 PM KCC Agent: DAVID WANN

Actual Plugging Report:

Perfs:

1st. Plug 3430' w/25 sxs.  
2nd. Plug at 1445' w/25 sxs.  
3rd. Plug at 800' w/100 sxs.  
4th. Plug at 260' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

RECEIVED  
NOV 22 2010  
KCC WICHITA

District: 04

Signed  (TECHNICIAN)

CM

Form CP-2/3

NOV 17 2010