

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20014-00-01
Spot: NW Sec/Twnshp/Rge: 18-20S-39W
4256 feet from S Section Line, 4022 feet from E Section Line
Lease Name: WATSON Well #: 1-A
County: GREELEY Total Vertical Depth: 2836 feet

Operator License No.: 7271
Op Name: BARTLING OIL COMPANY
Address: 1001 CANYON EDGE DR
AUSTIN, TX 78733

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1672		
SURF	8.625	393		WITH 300 SX CMT
PROD	4.5	2832	0	WITH 150 SX CMT

Well Type: SWD UIC Docket No: D24159.0 Date/Time to Plug: 10/28/2010 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GUS OCHSNER Company: BARTLING OIL Phone: (620) 376-2249

Proposed Plugging Method: FILL CASING WITH 400# HULLS & 110 SX CMT. FILL ANNULUS.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/28/2010 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SQUEEZED @ 1200' WITH 50 SX CMT, 900' WITH 50 SX CMT, 1390' WITH 100 SX CMT, 1690' & 1470' WITH 75 SX CMT. 160 SX CMT DOWN ANNULUS. CIBP WITH CMT @ 1672'. FILL 4 1/2" CASING WITH CMT FROM 1642' TO 0' USING 400# HULLS & 150 SX CMT. PRESSURED TO 500# & HELD. PUMP 2 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS TO 200#.

Perfs:

Top	Bot	Thru	Comments
1630	1642		
1510	1565		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
NOV 16 2010
KCC DODGE CITY

Signed *Ken Jehlik*
(TECHNICIAN)

RECEIVED
DEC 01 2010
KCC WICHITA