

To: 6 061264
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-5-87
API NUMBER 15- 051-21,698-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Operator: Graham Michaelis Corp
Name &
Address Box 247
Wichita, Kansas 67201

NW, SEC. 23, T 13 S, R 18 W/E
3300 feet from S section line
3300 feet from E section line

Lease Name Pfeifer Well # 1-23
County Ellis 119.76

Well Total Depth 3685 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 560

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Kansas 67524

Company to plug at: Hour: 12:30 PM Day: 5 Month: June Year: 19 87

Plugging proposal received from Dallis Foles

(company name) Kelso Casing (phone) 316-938-2457

were: Order 150 sks 65/35 Pozmix 10% Gel-2% Econolite, 5 sks Hulls.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:00 PM Day: 5 Month: June Year: 19 87

ACTUAL PLUGGING REPORT 8 5/8" set at 560' w/280 sks. 4 1/2" set at 3683' w/150 sks.

Top perf. at 3288'. Plugged bottom w sand and 4 sks. cement to 3225'.

Shot pipe 2 times and recovered 2900'. Pumped in 8 5/8". 5 sks Hulls, 150 sks cement w/1500 Psi.

RECEIVED
STATE CORPORATION COMMISSION

JUN 23 1987

6-23-87

CONSERVATION DIVISION
Wichita, Kansas

Remarks: By Allied.
(If additional description is necessary, use BACK of this form.)

~~It is recommended that you observe this plugging.~~

Signed Gilbert G. Scheck
(TECHNICIAN)
Gilbert G. Scheck

DATE 6-24-87

INV. NO. 17324