

To: 6 031098
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-3-88 210
API NUMBER 15- 051-20,625-00-01
SW NE NE, SEC. 23, T 13 S, R 18 (W)

TECHNICIAN'S PLUGGING REPORT

Operator License # 5145

Operator: Dreiling Oil Inc.
Name & Address Box 1000
Victoria, Ks. 67671

4290 feet from S section line
3630 feet from E section line

Lease Name Leiker Well # 1

County Ellis 114.04

Well Total Depth 3509 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 609

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated Alt 1 Comp

Plugging Contractor Allied Cement License Number _____

Address Plainville, Ks.

Company to plug at: Hour: AM Day: 3 Month: June Year: 19 88

Plugging proposal received from Ivan Edsall

(company name) Dreiling Oil (phone) _____

were: 8 5/8" set @ 609' w/ 305 sx. 4 1/2" set @ 3350" w. 125 sx. Perfs 3482-84" and
3440-44'. Order cement for bottom, pull pipe. Order 150 sx cement blend w/ 5 sx hulls.
Allied Cement Co. water trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:45AM Day: 3 Month: June Year: 19 88

ACTUAL PLUGGING REPORT Sand Bottom to 3430' w/ 4 sx of sand w/bailer. One shot recovered
2400' casing. Squeezed 8 5/8" w/200 sx cement, w/ 5 sx hulls mixed in. Max psi
to 600#. 400# close in psi. Plug complete

RECEIVED
STATE CORPORATION COMMISSION
7-6-88
JUL 6 1988

Remarks: Elev. 21146 Na
(If additional description is necessary, use BACK of this form.)

INVOICED
(Do not observe this plugging.)

DATE 7-12-88

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow

INV. NO. 2127(4)

6-3 AUG 13 1988