

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-23 363-00-00

NE-NE-NW Sec. 18, T 13 S, R 19 W

330 feet from N/A section line

1980 feet from W/A section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6657

Lease Name Disney Well # 1

Operator: Big Creek Oil Oper.
Name &

County Ellis

Address P.O. 1196
Hays, Ks 67601

Well Total Depth 3949 feet 128.35

Conductor Pipe: Size - feet -

Surface Casing: Size 8 3/8" feet 251 w/160 sks
60/40

Abandoned Oil Well Gas Well Input Well SWD Well D&A Sum

Other well as hereinafter indicated -

Plugging Contractor Sun Cementing - Pfeifer well serv. - Hill City, Ks
License Number -

Address Hays, Kansas 67601

Company to plug at: Hour: 11:00AM Day: 18 Month: 4 Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO LeRoy Hunt

(company name) Big Creek Oil (phone) -

were: 4 1/2" @ 3928 w/175 sk Perfs @ 3585-89 (2 perf);
3563-67, 3539-43' & 3810-18 (1 per ft.) P.B. 4 sks cmt.
sand to 3500', 4 sks cmt. Ordered 250 sk 5/8" ppg, 10% gel,
3% cc, w/ 1/4" flo-ual pr. sk, 20 sks gel, 4 hulls, 4 8 3/8" w. plug.
Recomm 25 jts of 4 1/2" csg. (720'): Shot hole @ 1927' 1425'

Signed Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:30pm. Day: 18 Month: 4 Year: 19 84

ACTUAL PLUGGING REPORT Impd in 4 sk gel, w/hulls
8 sk gel w/hulls, 100 sk cmt w/hulls, 8 gel w/hulls

Rel. lvs 180 sk cmt
Max 400 #
Shut-in 150 #

Remarks: -

RECEIVED
STATE CORPORATION COMMISSION

APR 30 1984
4-30-84
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did) did not) observe this plugging.

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED

DATE 4-30-84

INV. NO. 1279

4-18

MAY 03 1984