

4-041757

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

12-28-95

API Number: 15-051-22,773-00-00

NE /4 SEC. 18, 13 S, 19 W
1680 feet from N section line
1030 feet from E section line

Operator license# 5134

Lease: Disney B Well # 3-18

Operator: Graham-Michaelis Corporation

County: Ellis

Address: P.O. Box 247
Wichita, Kansas 67202

Well total depth 3785 ^{123.01} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 367 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 28 Month: December Year 1995

Plugging proposal received from: Norman Rodi

Company: Graham-Michaelis Corporation Phone: _____

Were: 4 1/2" casing set at 3784' w/150 sxs cement. Perfs at 3650' - 3725'.
Ordered 200 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus-500# hulls - plus 10 sxs gel.
D.V. Tool set at anhydrite and cement circulate to surface.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:00 P.M., Day: 28, Month: December, Year: 1995

Actual plugging report: R.U. Allied Cementing to squeeze. 4 1/2" casing as follows:
25 sxs cement with 200# hulls, followed with 10 sxs gel, followed with 150 sxs cement with
200# hulls. Max. P.S.I. 1000#. Hooked-up to 8 5/8" S.P. to 300# P.S.I. No cement
pressured-up.

RECEIVED
KANSAS CORP COMM
1996 MAR 25 A 11:39
3-25-96

Remarks:
Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES CALC NO Dakota plug: YES NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did[] / did not[X] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

HD

DATE MAR 25 1996

INV. NO. 45103