

4-071101

7-5

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-22,217-0000

SE SW SE /4 SEC. 18, 13 S, 19 W
290 feet from S section line
1650 feet from E section line

Operator license# 5134 Lease Adams well #3-18

Operator: Graham-Michaelis Corporation County Ellis

Address: P.O. Box 247 Well total depth 3835 feet ^{124.63}
Wichita, Kansas 67201 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 326 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement - Maier Pulling Unit License# -

Address: Hays, Kansas 67601 - Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 5 Month: July Year: 94

Plugging proposal received from: Norman Rodie

Company: Graham Michaelis Corporation Phone: 316-264-8394

Were: 8 5/8" - 326' S.P. cwc. w/210 sx. 4 1/2" casing set at 3866'
w/175 sx. cement. 4 1/2" casing squeezed at 719' to 1247' w/200 sx.
cement. PBSD 3774' - Elv. 2099' - Anhy. 1427' - Casing poor. Proposal
250 sx. 60/40 pozmix - 5 sx. hulls pump in with pump truck - spot and
displace all cement through tubing. 1) Perf. 4 1/2" casing at 2125' and
1440'. 2) With tubing spot and displace cement - load casing bottom to
top then squeeze 4 1/2" casing. Squeeze 4 1/2" x 8 5/8" annulus with
cement. Shut in under pressure.

Plugging Proposal Received by: Dennis Hamel - Marion Schmidt
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:00P.M., Day: 5, Month: July, Year: 94

Actual plugging report: Graham Machaelis ordered 300 sx. 60/40 pozmix -
10% gel - 5 sx. hulls. Spotted and displaced all cement through tubing.
1) Perferated 4 1/2" casing at 2125' and 1440'.
2) 2 3/8" tubing at 3846'-spot & displace 100 sx.cmt.w/3 sx.hulls added.
3) 2 3/8" tubing at 1666'-pumped in 80 sx.cmt.w/3 sx. hulls. Cement
circulated.
4) Squeezed 4 1/2" x 8 5/8" annulus w/15 sx. cement. Max.Pressure 300
P.S.I. Shut in 300 P.S.I.
5) Squeezed 4 1/2" casing w/20 sx.cmt. Max pressure 900 P.S.I. Shut in 400#.

Remarks: Cemented by: Allied Cement.
Condition of casing(in hole):GOOD BAD X Anhy.plug:YES X NO
Bottom plug(in place):YES X ,CALC ,NO Dakota plug:YES X ,NO
Plugged through TUBING X , CASING . Elevation: 2099 GL

I did X / did not[] observe the plugging.

INVOICED
DATE 7-14-94
INV. NO. 40820

Marion Schmidt
(agent)
RECEIVED
STATE CORPORATION COMMISSION
JUL 11 1994
Form CP-213 CONSERVATION DIVISION
Wichita, K