

4-071171

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-24,916-0000

3-19

SW SE NE /4 SEC. 09, 13 S, 18 W
2310 feet from section line
990 feet from E section line

Operator license# 5347

Lease: Pfeifer Well # 1

Operator: Condor Oil Company, Inc.

County: Ellis 121.22

Address: 310 West Central - #202
Wichita, Kansas 67202
Ralph Hamilton

Well total depth 3730 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 303 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Duke Drilling, Inc. License# 5929

Address: Great Bend, Kansas 67530

Company to plug at: Hour: A.M. Day: 19 Month: March Year: 1996

Plugging proposal received from: Harvey Moore

Company: Duke Drilling, Inc. Phone: 316-267-1331

Were: 8 5/8" - 303' S.P. cwc. w/180 sxs 60/40 pozmix - 2% gel - 3% c.c. By Allied Cement.
Elv. 2149' - Anhy. 1415' -Arbuckle 3750'. Mud condition 50 vis. - 9.1 wt. - 9.5 water loss
5.000 ppm cl at 3651'. No circulation problems. Proposal 215 sxs 60/40 pozmix - 6% gel and
1/4# flocele per sack - circulate hole 42 -45 vis. - spot and displace all cement through
drill pipe - heavy mud between all plugs. 25 sxs at 3690' - 25 sxs at 1420' - 100 sxs at
750' - 40 sxs at 350' - 10 sxs 40' - 15 sxs in rathole (circulate).

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 2:00 P.M. Day: 19 Month: March Year: 1996

Actual plugging report: Duke Oil ordered 215 sxs 60/40 pozmix - 6% gel and 1/4# flocele per sack. Spotted and displaced all cement through drill pipe with heavy mud between all plugs.
1st. Plug at 3690' w/25 sxs. cement.
2nd. Plug at 1420' w/25 sxs. cement.
3rd. Plug at 750' w/100 sxs. cement.
4th. Plug at 350' w/40 sxs. cement.
5th. Plug at 40' w/10 sxs. cement. - 15 sxs in rathole (circulated)

RECEIVED
KANSAS CORP COMM
MAR 25 A 11:39
325-96

Remarks: Cemented by Allied Cement.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING Elevation: GL

I did not observe the plugging. [X]

Marion J. Schmidt (agent)

INVOICED
DATE MAR 26 1996
INV. NO. 45127
3-19

MAY 17 1996