

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22011-00-01 ; **"CORRECTED"**
Spot: SESWNW Sec/Twnshp/Rge: 22-11S-16W *6016 ALP
NVD 2/20/11*
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: COMEAU B Well #: 1
County: ELLIS Total Vertical Depth: 3450 feet

Operator License No.: 8925
Op Name: LIBERTY OPER & COMPL, INC
Address: 308 W MILL
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	273	0	140 sx
L1	2.375	3415	0	cwc
PROD	4.5	3423	0	155 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/21/2011 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: ROGER COMEAU Company: LIBERTY OPER & COMPL, INC Phone: (785) 434-4686

Proposed Plugging Method: Ordered 160 sxs 60/40 pozmix - 4% gel - 300# hulls.
02/17/2011 - Superior perfed at 3073' - 1450' - 1015' - 580' - Blew 2 3/8" tubing up hole 5'.
High fluids.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/21/2011 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with 1" tubing to 3072'.
Allied rigged to 1" tubing and pumped 25 sxs cement.
Pulled tubing to 1536'. Allied rigged to tubing and pumped 50 sxs cement to circulate cement to surface.
Pulled 1" tubing. Rigged to 2 3/8" tubing and pulled 580' of 2 3/8".
Rigged to 4 1/2" casing and pumped 12 sxs cement.
Max. P.S.I. 500#. S.I.P. 400#.
Rigged to 8 5/8" - instant Max. P.S.I. 400#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3357	3360		PENN CONG
3233	3360		OA
3059	3680		KC

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed *Pat Staab*
(TECHNICIAN)

RECEIVED
FEB 28 2011
KCC WICHITA
Form CP-2/3
CM

FEB 22 2011