

16c1  
R

11-18

4-062545

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-051-24,770-00-00

SW SE NE /4 SEC. 28, 13 S, 17 W  
2970 feet from S section line  
990 feet from E section line

Operator license# 3715 Lease Dreiling well # 2

Operator: S.B. Oil County Ellis

Address: 3204 Willow Well total depth 3500 feet <sup>113.75</sup>  
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet  
913-628-4547 Surface pipe 8 5/8 Inch @ 250 feet

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Vonfeldt Drilling Company License# 9431

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 18 Month: November Year: 91

Plugging-proposal received from: Vonfeldt Drilling Company

Company: S.B. Oil Phone: 913-628-4547

Were: Order 400 sks. 60/40 posmix - 6% gel. - 3% cal. cl. -  
1/2 sk. flo-cel and 8 5/8" plug. Spot with drill pipe with no less  
than 36 vis. mud between all plugs, with good circulation and no  
fluid loss.

Lost circulation at 1555' in salt solution.

STATE CORPORATION COMMISSION  
RECEIVED  
NOV 25 1991  
WICHITA, KANSAS

Plugging Proposal Received by: Gilbert G. Scheck

Plugging operations attended by agent? All  ], Part  ], None

Completed: Hour: 3:30P.M. Day: 18 Month: November Year: 91

Actual plugging report:

1st. plug @ 1555' w/100 sks. of 60/40 posmix - 3% c.c. with 1/2 sk.  
flocele per sack.

2nd. plug @ 1221' w/100 sks. of 60/40 posmix - 3% c.c. with 10% gilsonite  
w/100 P.S.I.-hulls

3rd. plug @ 860' w/190 sks. of 60/40 posmix - 3% c.c. with 10% gilsonite  
w/no hulls.

15 sks. in Rathole. 10 sks. in Mousehole.

Remarks: Cemented by: Allied.

I (and     ) did not  ] observe the plugging.

*Gilbert G. Scheck*

**INVOICED**

DATE 12-6-91

INV. NO. 34020

(agent)  
Form CP-2/3