

4060205

5-28

051-04839-00-00 238 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 11-28-46

SW NE, SEC. 28, T 13 S, R 17 W/E

3300 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Drilling "C" Well # 1

Operator: Berexco, Inc.

County Ellis 106.11

Name & Address Box 723

Well Total Depth 3265 feet

Hays, KS 67601

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 117

Abandoned Oil Well XXXXXXXX Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Co. Tools License Number

Address

Company to plug at: Hour: 1:00PM Day: 28 Month: May Year: 19 91

Plugging proposal received from George Jorgenson

(company name) Berexco, Inc. (phone)

were: Order 350 sxs, 65/35pos 8%gel and hulls

Fish at 3151' packer and one joint of tubing.

RECEIVED  
STATE CORPORATION COMMISSION

Run tubing to fish and cement by displacement

7-3-91  
III 13 1991

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Herb Deines (TECHNICIAN)

Plugging Operations attended by Agent?: All XXXXXXXX Part None

Operations Completed: Hour: 3:30PM Day: 28 Month: May Year: 19 91

ACTUAL PLUGGING REPORT 10 3/4" to 117', 5 1/2" to 3257' Perf Anhydrite at 1210' and base of Dakota at 500'. Run tubing to fish and pump 100 sxs. cement. Laid down 1300' of tubing and pmp 100 sxs. cement. Laid down 1300' of tubing and circ cement to surf with 40 sxs.

Laid down tubing and tied onto casing. Pmp 50 sxs. cement with 50# hulls. Max 750# SIP 500#

Tied onto annulus. Instant pressure of 400#.

Remarks: B-J Services Cementing  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 7-18-91

Herb S.

Signed Herb Deines (TECHNICIAN)

INV. NO. 32270

Herb Deines

FORM CP-2/3  
Rev. 01-84