

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-073-21,403-0000

OWNER McConaughy

WELL NUMBER M-6

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2,970 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 36 TWP. 24S RGE. 12 (L) XXXX

COUNTY Greenwood

Date Well Completed 12-15-78

Plugging Commenced 11-18-86

Plugging Completed 11-21-86

LEASE OPERATOR Bird & Hanley

ADDRESS Route 1, Box 82, Toronto, Kansas 66777

PHONE (316) 637-2340 OPERATORS LICENSE NO. 5596

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Chanute, Kansas

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Bartlesville Depth to Top 1,621 Bottom 1,625 T.D. 1,675

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				7"	40'	None
				4 1/2"	1,674'	None

Describe in detail the manner in which the well was plugged, indicating where the mud filter was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

Set bottom hole plug from 1,675' to 1,570' with Portland A and 4% gel. Perforated at 700' then pumped plug to perforation and circulated cement to surface outside of casing and filled casing from 700' to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bird & Hanley License No. 5596

Address Route 1, Box 82, Toronto, Kansas 66777

STATE OF Kansas COUNTY OF Woodson, ss.

T. E. Bird

(XXXXXXXXXXXXXXXXXXXX) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) T. E. Bird

(Address) Rt. 1, Box 82, Toronto, Ks. 66777

STATE CORPORATION COMMISSION SUBSCRIBED AND SWORN TO before me this 9th day of December, 1986

DEC 11 1986

CONSERVATION DIVISION Commission Expires: 6-23-87  
Wichita, Kansas

Robert F. Hays  
Notary Public

**Robert F. Hays**  
NOTARY PUBLIC  
State of Kansas  
My Appointment Expires 6-23-87

Operator

Bird &amp; Hanley

DESIGNATE TYPE OF COMP.: OIL, GAS,  
DRY HOLE, SWDW, ETC.:

Oil Well

Well No.

- M-6

Lease Name

McConnaughey

15-073-21403-0000

S 36 T 24 R 12 E

330' FSL - 660' FEL NE/4

## WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,  
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil & clay	0	6		
Sandstone	6	10		
Shale	10	37		
Lime	37	40		
Lime with shale breaks	40	58		
Shale	58	70		
Shale with lime streaks	70	190		
Lime	190	202		
Shale	202	220		
Lime	220	240		
Sand	240	278		
Lime	278	282		
Shale with lime streaks	282	538		
Lime	538	652		
Shale	652	808		
Lime with shale streaks	808	843		
Sandy shale	843	881		
Sandy lime	881	912		
Sand	912	918		
Lime	918	949		
Lime with shale breaks	949	1014		
Shale	1014	1137		
Lime with shale breaks	1137	1171		
Shale	1171	1182		
Lime	1182	1185		
Lime	1185	1192		
Shale	1192	1263		
Lime with shale streaks	1263	1326		
Shale	1326	1334		
Lime	1334	1341		
Shale	1341	1424		
Sandy shale	1424	1578		
Shale	1578	1596		
Core # 1	1596	1622		
Core # 2	1622	1648		
Core # 3	1648	1657		
Shale	1657	1675		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Secretary

Title

STATE CORPORATION COMMISSION

3/20/79

Date

DEC 11 1986

CONSERVATION DIVISION  
Wichita, Kansas

KANSAS