

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-073-22,388-0000

LEASE NAME McConnaughey

WELL NUMBER M-11

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4,950 Ft. from S Section Line

1,320 Ft. from E Section Line

SEC. 36 TWP. 24 RGE. 12 (L) XXXX

COUNTY Greenwood

Date Well Completed 8-12-82

Plugging Commenced 11-18-86

Plugging Completed 11-20-86

LEASE OPERATOR Bird & Hanley

ADDRESS Route 1, Box 82, Toronto, Kansas 66777

PHONE# (316) 637-2340 OPERATORS LICENSE NO. 5596

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Chanute, Kansas

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Bartlesville Depth to Top 1,627 Bottom 1,647 T.D. 1,725

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				7"	225'	None
				4 1/2"	1,702'	None

Describe in detail the manner in which the well was plugged, indicating where the mud plug was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from foot to foot each set.

Set bottom hole plug from 1,725' to 1,575' with Portland A and 4 % gel. Perforated at 700' then pumped plug to perforation and circulated cement to surface outside of casing and filled casing from 700' to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bird & Hanley License No. 5596

Address Route 1, Box 82, Toronto, Kansas 66777

STATE OF Kansas COUNTY OF Woodson, ss.

T. E. Bird

(Signature) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) T. E. Bird

(Address) Rt. 1, Box 82, Toronto, Ks. 66777

SUBSCRIBED AND SWORN TO before me this 9th day of December, 1986

STATE CORPORATION COMMISSION

My Commission Expires: 6-23-87

Notary Public
Robert F. Hays
NOTARY PUBLIC
State of Kansas
My Appointment Expires 6-23-87

DEC 11 1986
10-11-86
CONSERVATION DIVISION
Wichita Kansas

OPERATOR Bird & Hanley LEASE NAME McConnaughey M-11-36 TWP. 24. R. 12E

FILL IN WELL LOG AS REQUIRED

Show all important zones of porosity and contents thereof, core intervals and all drill stem tests, including depth interval tested, cushion used, time test open flowing and shut in pressures, and core recovery.

SHOW GEOLOGICAL MARKERS LOGS RUN OR OTHER DESCRIPTIVE INFORMATION

FORMATION DESCRIPTION, CONTENTS, ETC	TOP	BOTTOM	MARKER	DEPTH
Soil	0	2		
Clay	2	22		
Lime hard	22	26		
Shale	26	37		
Lime hard	37	40		
Shale with lime streaks	40	81		
Lime	81	92		
Shale	92	115		
Lime	115	120		
Shale	120	153		
Lime	153	157		
Shale	157	162		
Lime	162	164		
Shale	164	167		
Lime	167	169		
Shale	169	198		
Lime	198	213		
Shale	213	228		
Shale with lime streaks	228	255		
Sand white	255	364		
Shale	364	381		
Lime	381	390		
Sand gray	390	400		
Shale	400	556		
Lime	556	670		
Shale	670	818		
Lime with shale streaks	818	849		
Shale	849	887		
Lime with shale streaks	887	959		
Shale with lime streaks	959	992		
Lime with shale streaks	992	1028		
Shale with lime breaks	1028	1191		
Lime	1191	1202		
Shale	1202	1230		
Shale with lime breaks	1230	1386		
Sand gray	1386	1396		
Shale	1396	1552		
Black Shale	1552	1557		
Shale	1557	1623		
Sand	1623	1646		
Shale	1646	1705		
Miss lime	1705	1711		
Break	1711	1716		
Lime	1716	1725		

STATE CORPORATION COMMISSION

DEC 11 1986

CONSERVATION DIVISION
Wichita, Kansas