

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-073-21,279-0000

LEASE NAME McConnaughey

WELL NUMBER M-2

2,970 Ft. from S Section Line

1,195 Ft. from E Section Line

SEC. 36 TWP. 24 RGE. 12 (E) of XXX

COUNTY Greenwood

Date Well Completed 10-19-79

Plugging Commenced 11-18-86

Plugging Completed 11-21-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Bird & Hanley

ADDRESS Route 1, Box 82, Toronto, Kansas 66777

PHONE#(316) 637-2340 OPERATORS LICENSE NO. 5596

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Chanute, Kansas

Is ACO-1 filed? If not, Is well log attached? Yes

Producing Formation Bartlesville Depth to Top 1,639 Bottom 1,647 T.D. 1,699

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				7"	60.5'	NONE
				4 1/2"	1,690'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from foot to foot each set.

Set bottom hole plug from 1,699' to 1,590' with Portland A and 4% gel. Perforated at 700' then pumped plug to perforation and circulated cement to surface outside of casing and filled casing from 700' to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bird & Hanley License No. 5596

Address Route 1, Box 82, Toronto, Kansas 66777

STATE OF Kansas COUNTY OF Woodson, ss.

T. E. Bird (XXXXXXXXXXXXXXXXXXXX) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) T. E. Bird

(Address) Rt. 1, Box 82, Toronto, Ks. 66777

STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 86

DEC 11 1986
10-11-86
CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires: 6-23-87

Robert F. Hays
NOTARY PUBLIC
State of Kansas
My Appointment Expires 6-23-87

Alco Drilling Co., Inc.

ROTARY DRILLING CONTRACTORS
Plugging, Work-Over & Fishing Service
318 SOUTH JEFFERSON
IOLA, KANSAS 66749

15-073-21279-0000

Well log
McConnaughey M-2
Greenwood County Kansas

0	24	Clay
24	26	Lime
26	31	Shale
31	34	Lime
34	45	Shale
45	48	Lime
48	60 $\frac{1}{2}$	Shale
60 $\frac{1}{2}$	62	Lime
62	126	Shale with lime streak
126	154	Sandy shale with shale
154	210	Shale with lime streaks
210	216	Lime
216	289	Shale with lime streaks
289	360	Sand
360	387	Shale with sandy shale
387	390	Lime
390	557	Shale with lime streaks
557	665	Lime with shale streaks
665	724	Shale with lime streaks
724	823	Shale
823	847	Lime with shale streaks
847	893	Shale with lime streaks
893	965	Lime with shale streaks
965	980	Shale with lime streaks
980	994	Lime with shale streaks
994	999	Shale
999	1032	Lime
1032	1151	Shale
1151	1213	Lime with shale streaks
1213	1268	Shale with lime streaks
1268	1353	Lime with shale streaks
1353	1365	Shale with lime streaks
1365	1397	Shale with sand streaks
1397	1590	Shale with lime streaks
1590	1602	Shale
1602	1607	Sand
1607	1621	Shale
1621	1628	Sand
1628	1698	Shale with sand streaks
1698	1699	Lime

STATE CORPORATION COMMISSION

DEC 11 1986

CONSERVATION DIVISION
Wichita, Kansas