

WELL NUMBER 15-073-22,957-000

LEASE NAME McConnaughey

WELL NUMBER 14

3,300 Ft. from S Section Line

1,320 Ft. from E Section Line

SEC. 36 TWP. 24 RGE. 12 (E) ~~XXXX~~

COUNTY Greenwood

Date Well Completed 9-10-83

Plugging Commenced 11-19-86

Plugging Completed 11-19-86

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Bird & Hanley

ADDRESS Route 1, Box 82, Toronto, Kansas 66777

PHONE#(316) 637-2340 OPERATORS LICENSE NO. 5596

Character of Well T.A.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Chanute, Kansas

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Bartlesville Depth to Top 1,639 Bottom 1,663 T.D. 1,735

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				7"	42 1/2'	None
				4 1/2"	1,728'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

Pumped portland A cement with 4% gel, from 1,735' to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bird & Hanley License No. 5596

Address Route 1, Box 82, Toronto, Kansas 66777

STATE OF Kansas COUNTY OF Woodson, Mo.

T. E. Bird (~~Employer~~) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) T. E. Bird

(Address) Rt. 1, Box 82, Toronto, Ks. 66777

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 86

Robert F. Hays  
 Notary Public

My Commission Expires: 6-23-87


**Robert F. Hays**  
 NOTARY PUBLIC  
 State of Kansas  
 My Appointment Expires 6-23-87

STATE CORPORATION COMMISSION  
 DEC 11 1986  
 12-11-86  
 CONSERVATION DIVISION  
 Wichita, Kansas

Louis McClain, President  
Dean Michael, Vice-President

15073-229570000

Iola, Kansas  
Telephone: 316-365-6013



# Alco Drilling Co., Inc.

ROTARY DRILLING CONTRACTORS  
Plugging, Work-Over & Fishing Service

RURAL ROUTE 3

IOLA, KANSAS 66749

Well Log

McConnaughey No. 14

Greenwood County Kansas

0	2	Clay
2	8	Red bed
8	11	Clay
11	13	Lime
13	15	Shale
15	22	Lime
22	33	Shale
33	38	Sand
38	42	Shale
42	42 $\frac{1}{2}$	Lime
42 $\frac{1}{2}$	67	Shale w/red bed
67	70	Lime
70	115	Shale
115	132	Sand grey
132	146	Shale
146	151	Lime
151	185	Shale
185	201	Lime w/shale break
201	235	Shale
235	248	Lime
248	265	Shale
265	269	Lime
269	374	Sand white
374	405	Shale
405	418	Lime w/shale break
418	440	Sandy shale
440	579	Shale
579	695	Lime w/shale break
695	845	Shale w/lime
845	877	Lime w/shale
877	884	Shale sandy
884	887	Lime
887	913	Shale w/red bed
913	926	Shale
926	1002	Lime
1002	1061	Lime w/shale
1061	1200	Shale
1200	1205	Lime
1205	1211	Shale
1211	1212	Lime
1212	1225	Shale
1225	1244	Lime
1244	1305	Shale
1305	1319	Lime w/shale streaks
1319	1327	Shale



# Alco Drilling Co., Inc.

ROTARY DRILLING CONTRACTORS  
Plugging, Work-Over & Fishing Service

RURAL ROUTE 3

IOLA, KANSAS 66749

Well Log

McConnaughey No. 14

Greenwood County Kansas

Page 2

1327	1331	Lime
1331	1345	Shale
1345	1349	Lime
1349	1360	Shale
1360	1369	Lime
1369	1376	Shale
1376	1382	Lime
1382	1413	Shale
1413	1426	Sandy shale
1426	1482	Shale w/lime streak
1482	1545	Shale
1545	1560	Shale w/sandy shale
1560	1568	Shale w/sandy lime
1568	1634	Shale
1634	1638	Oil sand good odor
1638	1647	Sandy shale
1647	1650	Sand light odor
1650	1667	Sand w/shale light odor
1667	1729 $\frac{1}{2}$	Shale w/sandy shale
1729 $\frac{1}{2}$	1730	Miss lime
1730	1735	Miss lime no show