

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32781
Name: Roberts Resources, Inc.
Address 1: 2020 N. Tyler, Suite 106
Address 2: _____
City: Wichita State: KS Zip: 67212 + _____
Contact Person: Kent Roberts
Phone: (316) 721-2817
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Mississippi Depth to Top: 5026 Bottom: 5439 T.D. 5530
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 097-21599-00-00
Spot Description: 20' south & 70' west of
E/2, W/2, NE Sec. 21 Twp. 30 S. R. 18 East West
~~3899~~ 3899 Feet from North / South Line of Section
~~1726~~ 1726 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Kiowa
Lease Name: Cobb 1-21 Well #: 1-21
Date Well Completed: 10/02/2006
The plugging proposal was approved on: 11/02/2010 (Date)
by: Steve Bond (KCC District Agent's Name)
Plugging Commenced: 11/16/2010
Plugging Completed: 11/16/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Surface	Water	Surface	8-5/8"	618'	none
Mississippi	Oil, Gas, Water	Production	5-1/2"	5230'	2040'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP @ 5000' w/ 2 sx cement on top. Shot casing at 2040' and pulled.
15 sx gel and 50 sx cement @ 1190'
50 sx cement @ 651'
25 sx cement @ 40' to surface

RECEIVED
DEC 10 2010

Plugging Contractor License #: 34227 Name: American Well Service, LLC
Address 1: PO Box 464 Address 2: _____
City: Pratt State: KS Zip: 67124 + _____
Phone: (620) 770-0621
Name of Party Responsible for Plugging Fees: Roberts Resources, Inc.
State of Kansas County, Sedgwick, ss.
Kent Roberts Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Kent Roberts

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
FEB 11 2011
KCC WICHITA