

LEASE NAME Charles

WELL NUMBER 2-25

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

330 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 25 TWP. 155 RGE. 42 ~~000~~ (W)

COUNTY Wallace

Date Well Completed 10/91

Plugging Commenced 12/11/96

Plugging Completed 12/12/96

LEASE OPERATOR Coastal Oil & Gas Corporation

ADDRESS 9 Greenway Plaza, #2751

PHONE# (713) 877-7590 Houston, TX 77046  
 OPERATORS LICENSE NO. 6593

Character of Well Gas oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/19/96 (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top 4980 Bottom 5086 T.D. 5300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Atoka	Oil		4846			
Mississippian			5148	8-5/8	322'	0
L. Morrow	Oil		5286	5-1/2	5299'	0
Morrow V-1	Oil		4896			
Morrow Shale			4986			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

~~Unseated pump POOH 68-7/8" & 134-3/4" rods w/pump. Unset tbg. anchor POOH 165 its 2-7/8"~~

~~the. Laved down in singles RDMO. R.U. Dowell tested lines to 1000 psi. Pump 1.5 bbis~~

~~wt down 8-5/8" pressure to 850 psi. Pump 50sx cmt 65/35 pozmix w/6% gel w/300# cotton seed~~

(If additional description is necessary, use BACK of this form.) (OVER)

Name of Plugging Contractor Dowell License No. \_\_\_\_\_

Address P O Box 887, Ylysses, KS 67880

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Coastal Oil & Gas Corporation

STATE OF Texas COUNTY OF Harris, ss.

Deborah Moore (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Deborah Moore

(Address) 9 Greenway Plaza, Ste. 2751

Houston, TX 77046

SUBSCRIBED AND SWORN TO before me this 26th day of February, 1997

[Signature]  
 Notary Public



TINA JORDAN  
 Notary Public, State of Texas  
 My Commission Exp. July 5, 1997

Expires: July 5, 1997

hulls down 5-1/2 csg. @ 4.0 BPM @ 10 psi pump 2700# gel spear @ 4.0 BPM @ 10 psi. pump  
250 sx 65/35 pozmix class H cmt w/6% gel to surface max psi 25 max rate 4.0 BPM. ISIP  
20 psi R.D. Dowell

Dug cellar & cement 5-1/2 csg. 4' below G.L. Hauled tbg. & rods to Elkhart yard #13. Level  
& restore location