


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Butler County, Sec. 11 Twp. 25S Rge. 7 (E) E 1/4 W
Location as "NE/CNWXSWX" or footage from lines SE SE NE 1/2 2/2 3/2 4/2
Lease Owner Dianne McCarthy
Lease Name Roy Well No. 5
Office Address R. R. #2, Eureka, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Nov. 2 19 66
Application for plugging filed Nov. 3 19 66
Application for plugging approved Nov. 3 19 66
Plugging commenced Nov. 3 19 66
Plugging completed Nov. 3 19 66
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production ----- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin
Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 2515 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	208	150 SX

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ----- feet to ----- feet for each plug set.

Filled hole with mud from T.D. up to 220'. Put in 1/2 sack of hulls & plug and 20 sacks cement.
Filled on up with mud to 30'. Put in 1/2 sack hulls & plug and 8 sacks cement.
Put 2 sacks cement in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Berentz Drilling Company
Address Box 428, Eureka, Kansas

STATE OF Kansas, COUNTY OF Greenwood, ss.
Jack Berentz (Employer or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack Berentz
Box 428, Eureka, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of November, 1966

Nelle M. Kirkpatrick
Notary Public.

My commission expires October 26, 1967

15-015-30395-0000 P

LOG OF WELL

ROY NO. 5

Loc: SE SE NE
Sec. 11-25S-7E
Butler County, Kansas

OPERATOR: Dianne McCarthy
CONTRACTOR: Berentz Drilling Co.

Commenced with rotary October 28, 1966
Completed with rotary November 2, 1966

CASING: 8 5/8" x 208.85' cemented with 150 sacks

FORMATION

Soil & gravel	15
Lime	160
Lime & shale	216
Shale & lime	965
Lime & shale	1200
Shale & lime	1462
Shale & shells	1743
Lime (Lansing)	1888
Shale & lime	2034
Lime (KC)	2204
Shale & lime strks	2463
Shale & few sand strks	2515 R.T.D.

Cored from 2463-2515
Plugged & abandoned November 3, 1966

NOV 14 1966
CONSERVATION DIVISION
Butler County, Kansas