

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-051-00800-00-00
WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Ellis County. Sec. 2 Twp. 13 Rge. 18 (X) (W)
Location as "NE/CNW&SW&" or footage from lines NW NW SE
Lease Owner Doley Oil Company
Lease Name Rankin Well No. 2
Office Address Hays, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 27 19 54
Application for plugging filed September 27 19 54
Application for plugging approved September 27 19 54
Plugging commenced 1:00 P.M. September 27 19 54
Plugging completed 2:30 P.M. September 27 19 54
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, by telephone

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	138 ft.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to

feet for each plug set.
Filled hole with mud. Ran plug and squeezed 80 sacks cement in hole.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kiefer & Krause Drilling Co., Inc.
Address Post Office Box 396, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON
Richard B. Krause contractor for owner
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard B. Krause
for Kiefer & Krause Drilling Co., Inc.
Box 396 Great Bend, Kansas

SUBSCRIBED AND SWORN to before me this 12th day of October, 1954

My commission expires 4-11-55 Notary Public.

PLUGGED
2 13 116
67 21

DRILLERS LOG

COMPANY: DOLEY OIL COMPANY

SEC: 2 T13S R18W

FARM: Rankin No. 2

LOC: NW NW SE
Ellis County, Kansas

TOTAL DEPTH: 3730'

COMM: 9-18-54 COMP: 9-27-54

CONTRACTOR: Kiefer & Krause Drilling Co., Inc.

CASING: 8 5/8" 138'

ELEVATION: 2159' RB

15-051-00800-00-00
15-051-00800-00-00

0	70	Post Rock
70	123	Sand
123	220	Blue Shale
220	470	Shale & Shells
470	535	Sandy Shale
535	650	Shale & Sand
650	700	Sand
700	1090	Shale & Shells
1090	1195	Red Bed
1195	1419	Red Bed & Shale
1419	1458	Anhydrite
1458	1830	Shale & Shells
1830	2000	Shale
2000	2500	Shale & Lime
2500	2780	Lime & Shale
2780	2965	Shale & Lime
2965	3350	Lime & Shale
3350	3720	Lime
3720	3730	Dolomite

Cemented 8 5/8" Casing at
138 ft. with 135 sacks of
cement and 2 sacks Calcium
Chloride.

3730 Total Rotary Depth. Filled hole with mud; ran
plug and squeezed 80 sacks
cement in hole.

I certify that this is the true and correct copy of the above
log, to the best of my knowledge.

Lila J. Krause
for Kiefer & Krause Drilling Co., Inc.

Subscribed and sworn to before me this 30 day of September, 1954.

John W. Rose
Notary Public

My Commission Expires 4-11-55

