


STATE OF KANSAS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 P. O. BOX 17027
 WICHITA, KANSAS 67217

15-051-20987-00-00
 15-051-20987-00-00
WELL PLUGGING RECORD

FORM CP-4



Locate well correctly on above Section Plot

Ellis County, Sec 2 Twp 13S Rge (E) 18 (W)
 Location as "NE/CNW/SE/SW" or footage from lines SE NW NW
 Lease Owner Petroleum, Inc.
 Lease Name McRae Well No. 1
 Office Address R. H. Garvey Building, 300 W. Douglas, Wichita, Ks.
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed November 20 1974
 Application for plugging filed November 20 1974
 Application for plugging approved November 20 1974
 Plugging commenced November 20 1974
 Plugging completed November 20 1974
 Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3656'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 550' w/50 sacks Pozmix, 6% Gel. Come up hole to 215' - set plug w/25 sacks pozmix, 6% Gel. Top plug set @ 40' w/1/2 sack hulls and 10 sacks pozmix, 6% Gel.

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 25 1974
 CONSERVATION DIVISION
 Wichita, Kansas

Name of Plugging Contractor Duke Drilling Company
 Address Box 823, Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON
Wayne Dobbs (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne Dobbs
Box 823, Great Bend, Kansas

Subscribed and sworn to before me this 22nd day of November, 1974

My commission expires April 11, 1978
Maahy M. Hague Notary Public.

DRILLERS' WELL LOG

15-051-20987-00-00

15-051-20987-00-00

DATE COMMENCED: November 11, 1974
DATE COMPLETED: November 20, 1974

Petroleum, Inc.
McRAE # 1
SE NW NW Sec. 2-T13S-R18W
Ellis County, Kansas

ELEVATION: 2076 KB

0 - 60'	Surface Clay
60 - 447'	Shale, Shells
447 - 476'	Sand
476 - 800'	Shale, Shells
800 - 990'	Shale, Sand
990 - 1200'	Shale and Shells
1200 - 1335'	Shale, Red Bed
1335 - 1377'	Anhydrite
1377 - 1610'	Shale, Shells, Red Bed
1610 - 3306'	Lime and Shale
3306 - 3310'	Shale
3310 - 3357'	Lime and Shale
3357 - 3628'	Lime
3628 - 3656'	Dolomite
3656'	RTD

FORMATION TOPS

Anhydrite	1335
Heebner	3306
Lansing (KC)	3357
Arbuckle	3628
RTD	3656

SURFACE PIPE: Set 206' of 8 5/8" new 20# pipe with 125 sacks common cement, 2% gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS }
COUNTY OF BARTON } ss.

RECEIVED
STATE CORPORATION COMMISSION
NOV 25 1974
CONSERVATION DIVISION
Wichita, Kansas

Wayne Dobbs, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Wayne Dobbs

Subscribed and sworn to before me this 22nd day of November, 1974.

Stanley M. Hagne

My Commission Expires: April 11, 1978

RECEIVED
STATE CORPORATION COMMISSION
NOV 25 1974
CONSERVATION DIVISION
Wichita, Kansas