

KANSAS STATE CORPORATION COMMISSION CONSERVATION DIVISION AGENT'S REPORT

RECEIVED SEP 26 1966 09-26-1966 CONSERVATION DIVISION Wichita, Kansas

J. P. Roberts Assitant Director 500 Insurance Building 212 North Market Wichita 2, Kansas

Operator's Full Name Heller Drilling Company Inc. Complete Address: 1014 Union Center Building, Wichita, Kansas Lease Name Gerber Well No. 1 Location SW SW NW Sec. 15 Twp. 13 Rge. 20 (E) (W) X County Ellis Total Depth 3898' Abandoned Oil Well Gas Well Input Well SWD Well D & A X Other well as hereafter indicated: Plugging Contractor: Co. Tools Address: License No. Operation Completed: Hour 10:30 A Day 23 Month 9 Year 1966

The Above well was plugged as follows:

RTD 3898' 8 5/8 csg set at 215' cwc 165 sc. Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 25 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/3 sc hulls and 8 sc cement to base of celler. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature] Well Plugging Supervisor

DATE 9/26/66 INV. NO. 3985-W