

15-051-20157-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
MAY 20 1967
11-20-1967
CONSERVATION DIVISION

Operator's Full Name Clinton Oil Company
Complete Address: 6810 W. Highway 54 Wichita, Kansas
Lease Name Wegele Well No. 1-V
Location E/2 SW/4 NE/4 Sec. 15 Twp. 13 Rge. 20 (E) (W) X
County Ellis Total Depth 3869
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Garvey Drlg. Co.
Address: Wichita, Kansas License No.
Operation Completed: Hour 11: A Day 16 Month 11 Year 1967

The Above well was plugged as follows:

RTD 3869' 8 5/8 csg set at 252' cwc 185 sc.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 100 sc cem.
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: P. J. Massey
Well Plugging Supervisor

INVOICED

DATE 11/21/67
INV. NO. 6723-4