

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED

STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

JAN 10 1975
OIL - 75
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name H. W. Gill
Complete Address 243 N. Emporia Wichita, Kansas 67202
Lease Name Keller (Deutscher) Well No. 1
Location SW SE SE Sec. 2 Twp. 13 Rge. (E) (W) 21
County Trego Total Depth 3865'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Chas. Crowe Casing Pulling
Address Box 706 Hays, Kansas 67601 License No. 733
Operation Completed: Hour 11 A Day 9 Month 1 Year 1975

The above well was plugged as follows:

- Total Depth 3865' 8 5/8 csg set at 200' cwc 150 sk.
- 5 1/2 csg set at 3865' cw 100 sk cmt.
- 5 1/2 csg 2-stage collar at A/1600' & circ to surface with cement.
- Pushed 5 1/2 wood plug from 0 to 3775' -dumped 4 sk cem W/dump bailer. (3775-3745)
- No pipe recovered. Set rock & sand bridge (725-700)
- Filled with RM cem from 700' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Mason
Well Plugging Supervisor

INVOICED

DATE 1/10/75

INV. NO. 631-W