

15-051-30330-00-00

FORM - CP-2  
Rev. 9-8-64

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 26 1966  
09-26-1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Musgrove of Hellar Drlg. Co. Inc. has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Hellar Drilling Co. Inc.

Complete Address: 1014 Union center Bldg. Wichita, Kansas

Lease Name: Gerber Well No. 1

Location: SW SW NW Sec. 15 Twp. 13 Rge. 20 (E)(W) X

County Ellis Total Depth 3898' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Musgrove was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and  
displace 25 sc cement thru drill pipe. Heavy mud to 210' set cementing  
plug and displace 20 sc cement thru drill pipe. Heavy mud to 40' set  
cementing plug, 1/3 sc hulls and 8 sc cement to base of celler.

Plug rat hole with 2 sc cement.

Very truly yours,

Leo Massey  
Conservation Division Agent