



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

STATE CORPORATION COMMISSION

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

DEC 16 1963  
 12-16-63  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Co.

Complete Address: 1425 Wichita Plaza, Wichita, Kansas

Lease Name: Shanline Well No. # 1

Location: C SW NW Sec. 27 Twp. 26 Rge. 11 (E) (W) W

County Pratt Total Depth 4515 Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Walker was instructed to plug the well as follows:

374' of 8 5/8" surface pipe, cemented with 200 sacks.  
Fill hole with drilling mud to 300', 1st cementing plug,  
bridge with hulls, cement with 25 sacks. Fill hole with  
drilling mud to 40', 2nd cementing plug, bridge with hulls,  
cement with 10 sacks to base cellar. Bridge and cement rat  
hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent