

State of Kansas



15-19520006-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
FEB 27 1967  
02-27-67

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company, Incorporated,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Deutscher Well No. 1

Location: NE-SW-SE Sec. 2 Twp. 13 Rge. (E)(W) 21

County Trego Total Depth 3850 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Walker was instructed to plug the well as follows:

213'--8 5/8" Surface pipe, cement circulated with 160 Sx.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

"	"	210'	with $\frac{1}{2}$ sk. hulls &
			20 Sx. cement.
"	"	40'	with $\frac{1}{2}$ sk. hulls &
			10 Sx. cement.

Very truly yours,

W. L. Nichols  
Conservation Division Agent