



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ed Weiler of Shields Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Incorporated,

Complete Address: Shields Building, Russell, Kansas.

Lease Name: Helget Well No. 1

Location: SW-NE-NW Sec. 2 Twp. 13 Rge. (E)(W) 21

County: Trego Total Depth 3485' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Weiler was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 1125'.

Circulate hole with heavy mud. Pull DP to 1350' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUN 23 1969
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Conservation Division Agent