

15-051-30365-00-00

FORM - CP-2
Rev. 9-8-64

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

JUL 7 1964
07-07-1964
STATE CORPORATION COMMISSION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Cook of Abercrombie Drilling Co. has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling Company Inc.

Complete Address: 801 Union Center Wichita, Kansas

Lease Name: Rankin Well No. 2

Location: SW SE SE Sec. 33 Twp. 13 Rge. 20 (E)(W) X

County Ellis Total Depth 3915 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

 Gun pits, circulate heavy mud, set cementing plug at 540 Ft.
and displace 20 sc cement thru drill pipe. Heavy mud to 240 Ft. set
cementing plug and displace 20 sc cement thru drill pipe. Heavy mud
to 40 Ft. set cementing plug, 1/2 sc hulls and 10 sc cement to base
of celler. Plug rat hole with 2 sc cement.

Very truly yours,

 Leo Murray
Conservation Division Agent