


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-195-00157-00-00

NORTH

Locate well correctly on above
Section Plat

Trego

County. Sec. 4 Twp. 13S Rge. 21W (E) (W)Location as "NE/CNW/SW" or footage from lines SE SE SELease Owner Imperial Oil of Kansas, Inc.Lease Name Keller Well No. 1Office Address 903 Union National Bank, Wichita 2, KansasCharacter of Well (completed as Oil, Gas or Dry Hole) Dry HoleDate well completed July 31, 1956Application for plugging filed July 31, 1956Application for plugging approved July 31, 1956Plugging commenced July 31, 1956Plugging completed July 31, 1956Reason for abandonment of well or producing formation No shows of oilIf a producing well is abandoned, date of last production 19Was permission obtained from the Conservation Division or its agents before plugging was commenced? YesName of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, KansasProducing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3935 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	7-31-56	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole at 300 feet with 25 sacks
cement. Set No. 2 plug at 75 feet with
25 sacks cement.

STATE CORPORATION COMMISSION

AUG 14 1956
08-14-56
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.Address 903 Union National Bank Building, Wichita 2, KansasSTATE OF Kansas, COUNTY OF Sedgwick, ss.
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-describedwell, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.(Signature) By: Ray L. Bacon V-P
903 Union Nat'l. Bank Bldg. Wichita, Ks.
(Address)SUBSCRIBED AND SWORN TO before me this 13th day of August, 19 56My commission expires April 18, 1959Frances E. Barham
Frances E. Barham Notary Public.

PLUGGING

FILE SEC 4 T 13 R 21W
BOOK PAGE 81 L. E. 43

15-195-00157-00-00

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
903 Union National Bank Building
Wichita 2, Kansas

Keller No. 1
SE SE SE Sec. 4 -13S-21W
Trego County, Kansas

Total Depth: 3935'

Commenced: 7-17-56 Completed: 7-31-56

Elevation: 2215' R.B.
Production: D & A

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 319' with 225 sacks cement.

Figures indicate bottom of formations:

Surface Sand and Shale	540'		
Shale Shells and Sand	1380'		
Shale and Shells	1594'	<u>TOPS</u>	
Anhydrite	1641'	Anhydrite	1594' (/ 621)
Shale and Shells	2250'	Heebner	3474' (-1259)
Shale and Lime	2525'	Lansing	3509' (-1294)
Lime	2605'	Conglomerate	3879' (-1664)
Shale and Lime	3450'	Arbuckle	3916' (-1701)
Lime	3835'	Total Depth	3935' (-1720)
Lime and Chert	3905'		
Lime	3935'		
Total Depth	3935'		

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

RECEIVED
STATE COMMISSION

IMPERIAL OIL OF KANSAS, INC.

AUG 14 1956

By: Ray L. Brown
Vice-President

CONSERVATION DIVISION

Subscribed and sworn to before me this 13th day of August, 1956.

My Commission Expires:

April 18, 1959

Frances C. Barham
Notary Public

