

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21214-00-00
Spot: SWNENW Sec/Twnshp/Rge: 29-17S-10W
4458 feet from S Section Line, 3551 feet from E Section Line
Lease Name: JANSSEN Well #: 1
County: ELLSWORTH Total Vertical Depth: 3400 feet

Operator License No.: 33186
Op Name: LB EXPLORATION, INC.
Address: 2135 2ND RD
HOLYROOD, KS 67450

String	Size	Depth (ft)	Pulled (ft)	Comments
<u>CIBP</u>	<u>5.5</u>	<u>3250</u>		
<u>SURF</u>	<u>8.625</u>	<u>571</u>		<u>250 SX</u>
<u>PROD</u>	<u>5.5</u>	<u>3398</u>	<u>1942</u>	<u>150 SX</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/17/2011 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: DS & W WELL SERVICING, INC. Phone: (620) 786-4258

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE
Date/Time Plugging Completed: 03/17/2011 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND TO 3130' AND CAP WITH 5 SX'S CEMENT. SHOOT CASING OFF AT 1942' AND PULL TO 1300' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS. PULL CASING TO 620' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3301	3307		
3179	3184	CSG	

Remarks: 60-40 POZ, 4% GEL, ALLIED TICKET #38778.

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

RECEIVED

APR 05 2011

KCC WICHITA