

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21066-00-00
Spot: S2NWSESW Sec/Twnshp/Rge: 19-14S-14W
880 feet from S Section Line, 3630 feet from E Section Line
Lease Name: REINHARDT B Well #: 1
County: RUSSELL Total Vertical Depth: 3246 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	630	0	200 SX
PROD	5.5	3244	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/01/2010 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Revd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 10 sxs gel.
Perf: 1200' - 850' - 410'.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2010 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3200' - pumped 10 sxs gel - followed with 50 sxs cement and 200# hulls.
Pulled tubing to 1650' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 680' - pumped 100 sxs cement - cement circulated.
POOH. Hooked up to casing and pumped 90 sxs cement.
Cement circulated out the Braden head at 100# P.S.I.
Shut in both casing and Braden head.

Perfs:

Top	Bot	Thru	Comments
3244	3246		OHIO

RECEIVED

Remarks: SWIFT CEMENTING SERVICE -TICKET #19351.

Plugged through: TBG

DEC 06 2010
12-6-10
KCC WICHITA

District: 04

Signed Ray A. Dinkel
(TECHNICIAN)

CM