

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20780-00-00
Spot: NWSESESW Sec/Twnshp/Rge: 30-10S-31W
410 feet from S Section Line, 2000 feet from W Section Line
Lease Name: HEMMERT Well #: 1-30
County: THOMAS Total Vertical Depth: 4650 feet

Operator License No.: 8628
Op Name: CREDO PETROLEUM CORPORATION
Address: 1801 BROADWAY # 900
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	248		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/13/2011 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: JAY Company: CREDO PETROLEUM CORPORATI Phone: (303) 297-2200

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN WitnessType: NONE
Date/Time Plugging Completed: 01/13/2011 1:45 AM KCC Agent: DAVID WANN

Actual Plugging Report:

1st. Plug at 2510' w/25 sxs.
2nd. Plug at 1670' w/100 sxs.
3rd. Plug at 290' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED
Form CP-2/3
JAN 20 2011

KCC WICHITA

JAN 14 2011