

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23703-00-00
Spot: NWNENWSE Sec/Twnshp/Rge: 22-8S-25W
2520 feet from S Section Line, 1765 feet from E Section Line
Lease Name: RICHMEIER Well #: 1-22
County: GRAHAM Total Vertical Depth: 3960 feet

Operator License No.: 8628
Op Name: CREDO PETROLEUM CORPORATION
Address: 1801 BROADWAY # 900
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	247		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/08/2011 9:00 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY Company: CREDO PETROLEUM CORPORATI Phone: (303) 297-2200

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE
Date/Time Plugging Completed: 01/08/2011 11:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st. Plug at 2120' w/25 sxs.
2nd. Plug at 1228' w/100 sxs.
3rd. Plug at 300' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

RECEIVED
JAN 14 2011
KCC WICHITA

District: 04

Signed [Signature]
(TECHNICIAN)

CM

Form CP-2/3

JAN 11 2011