

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-073-23398-00-00

Spot: SWSESESE

Sec/Twnshp/Rge: 23-23S-10E

100 feet from S Section Line,

360 feet from E Section Line

Lease Name: BURKETT

Well #: D-32

County: GREENWOOD

Total Vertical Depth: 2262 feet

Operator License No.: 33245

Op Name: CROSS BAR ENERGY, LLC

Address: 100 S MAIN STE 400
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

SURF	8.625	200		110 SX
------	-------	-----	--	--------

PROD	4.5	2197		125 SX
------	-----	------	--	--------

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/20/2010 9:00 AM

Plug Co. License No.: 34059

Plug Co. Name: HURRICANE SERVICES, INC.

Proposal Rcvd. from: STUART WOODIE

Company:

Phone: (620) 960-1218

Proposed Plugging Method: 20 SXS @ 2190'; 20 SXS @ 900'; 30 SXS @ 150' TO SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: PARTIAL

Date/Time Plugging Completed 12/21/2010 1:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

casing parted @ 900' unable to pull tubing hooked up to tubing pumped 25 sxs cement @ 2100', shot tubing off @ 900' pumped 25 sxs cement, pulled tubing out shot 4.5" @ 150' pumped 150 sxs cement to surface, gel spacers between cement plugs.

RECEIVED

DEC 27 2010

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

Mik [Signature]

(TECHNICIAN)

RECEIVED

JAN 03 2011

KCC WICHITA

Form CP-2/3