

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-20956-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 29-34S-2E  
1650 feet from N Section Line, 990 feet from W Section Line  
Lease Name: HERMAN WOLF Well #: 2  
County: SUMNER Total Vertical Depth: 3528 feet

Operator License No.: 30253  
Op Name: CYCLONE PETROLEUM, INCORPORAT  
Address: 7030C S LEWIS ST STE 541  
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	3074		
SURF	8.625	257		
PROD	4.5	3521		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/05/2010 8:00 AM  
Plug Co. License No.: \_\_\_\_\_ Plug Co. Name: \_\_\_\_\_  
Proposal Rcvd. from: DARREN BROYLES Company: CLYLONE PETROLEUM Phone: (620) 441-7223

Proposed Plugging Method: SET CIBP 50' ABOVE THE PERFS AND CAP WITH 2 SKS OF CMT. PERF CASING AT 300' AND CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: PARTIAL  
Date/Time Plugging Completed: 11/05/2010 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

NOT NOTIFIED OF PROBLEM IN GETTING TO BOTTOM UNTIL WE WERE ON LOCATION TO PLUG TOP. A CIBP WAS SET AT 1850', WHICH WAS APPARENTLY WHERE THE CASING WAS PARTED OR TUBING WAS STUCK IN HOLE. THE CASING WAS CAPPED WITH 2 SKS OF CMT. THE CASING WAS PERF'D AT 300', WHERE CMT WAS CIRC'D TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
3502	3526	CSG	

Remarks: CONSOLIDATED CMTG #29938 100 SKS OF 60/40 4% GEL

Plugged through: CSG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

Form CP-2/3

RECEIVED

DEC 15 2010

KCC WICHITA

JK