

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-22361-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 1-35S-2E  
430 feet from S Section Line, 330 feet from W Section Line  
Lease Name: WENTWORTH-SUNDANCE Well #: 5  
County: SUMNER Total Vertical Depth: 3250 feet

Operator License No.: 30253  
Op Name: CYCLONE PETROLEUM, INCORPORAT  
Address: 7030C S LEWIS ST STE 541  
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2160		
CIBP	4.5	3080		
SURF	8.625	258		150 SX
PROD	4.5	3250		275 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/15/2010 8:00 AM  
Plug Co. License No.: \_\_\_\_\_ Plug Co. Name: \_\_\_\_\_  
Proposal Rcvd. from: DARREN BROYLES Company: CONSULTANT Phone: (620) 441-7223

Proposed Plugging Method: SAND THE PERFS BACK TO 2000' AND CAP WITH 4 SKS OF CMT. PERF CASING AT 300' AND CIRC CMT TO SURFACE.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/05/2010 11:10 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE TOP PERFS WERE COVERED WITH SAND TO 2000', AND CAPPED WITH 4 SKS OF CMT. NO RECOVERY. THE CASING WAS PERFD AT 300' AND CMT WAS CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3136	3138	CSG	
2797	2798	CSG	
2063	2068	CSG	
1542	1544	CSG	
1471	1476	CSG	

Remarks: CONSOLIDATED CMT #29937 100 SKS 60/40 4% GEL

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
DEC 15 2010  
KCC WICHITA