

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21417-00-00  
Spot: NWSWNE Sec/Twnshp/Rge: 21-33S-6W  
3630 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: TURNER Well #: 2  
County: HARPER Total Vertical Depth: 4538 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	250		175 sxs
T1	2.375	4421		
PROD	4.5	4539	2340	175 sxs

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/08/2010 8:00 AM

Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC

Proposal Rcvd. from: FRITZLER Company: FRITZLER TRUCKING & WHITETA Phone: \_\_\_\_\_

Proposed  
Plugging  
Method:

CIBP AT 4400', 2 SKS CMT, REC CASING, 35 SKS 1200, 35 SKS 800', CIRC CMT 300-0

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: PARTIAL

Date/Time Plugging Completed: 12/08/2010 3:00 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

A CIBP WAS SET AT 4400', AND CAPPED WITH 2 SKS OF CMT. THE CASING WAS RECOVERED FROM 2340 AND PULLED TO 1200', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 700', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 300', WHERE CMT WAS CIRCULATED TO SURFACE.

Top	Bot	Thru	Comments
4448	4452	CSG	

Remarks: ALLIED CEMENTING 60/40 4% GEL

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
APR 11 2011  
KCC WICHITA